



## City of Garden Ridge

9400 Municipal Parkway  
Garden Ridge, Texas 78266-2600  
(210) 651-6632  
Fax (210) 651-9638

### AGENDA PLANNING AND ZONING COMMISSION REGULAR SESSION TUESDAY, MAY 10, 2016 -- 6:00 P.M.

---

The Garden Ridge Planning and Zoning Commission will meet in a scheduled regular at 6:00 p.m., Tuesday, May 10, 2016 in the City Council Chambers, 9400 Municipal Parkway, Garden Ridge, Texas. This is an open meeting, open to the public, subject to the Open Meetings Law of the State of Texas, and as required by law, notice is hereby posted on May 6, 2016 before 5:00 p.m., providing time, place, date and agenda thereof. The meeting facility is wheelchair accessible and accessible parking spaces are provided. Requests for accommodations or interpretive services must be made 48 hours prior to this meeting.

---

1. Call to Order
2. Roll Call
3. Citizen Comments – limited to 3 minutes each

#### **Rules for Citizen's Participation:**

The Planning and Zoning Commission welcomes citizen participation and comments at all of their Commission Meetings. As a courtesy to your fellow citizens and out of respect to our elected officials, we request that if you speak, that you please follow these guidelines.

- a) Direct your comments to the entire Commission, not to an individual member, nor to the audience.
- b) Show the Commission the same respect and courtesy that you would like to be shown.
- c) Limit remarks to three (3) minutes per citizen during Item 3 and to three (3) minutes per citizen during Item 6.
- d) Citizens' comments will be limited to one (1) hour in Item 3 and thirty (30) minutes in Item 6.
- e) Citizen comments may be deferred to a specific Business Item set forth in Section 4, below, if such comments pertain to such Business Item

*NOTE: The Texas Open Meetings Act permits a member of the public or a member of the governmental body to raise a subject that has not been included in the notice for the meeting. However, any discussion of the subject **must be limited** to a proposal to place the subject on the agenda for a future meeting and any response to a question posed to the Commission is limited to either a statement of specific factual information or a recitation of existing policy. TEX. GOV'T CODE § 551.042.*

4. Business Items

- a) Petition by Sahota Holdings, LLC c/o Ravinder Shota, for rezoning of a 2.080 acre tract at the southwest corner of FM 2252 and Nacogdoches Loop, from Residence Agriculture (RA) District to Neighborhood Service District (b-1) for a convenience store and car wash (Presentation only. Public Hearing scheduled for June 14, 2016).
- b) Petition by Sahota Holdings, LLC c/o Ravinder Shota, for Master Development Plan for a 2.080 acre tract at the southwest corner of FM 2252 and Nacogdoches Loop for a convenience store and car wash

5. Administrative Items

The Commission may discuss, consider and/or take possible action on the following items:

- a) Minutes of the April 12, 2016 Joint Meeting between the City Council and Planning and Zoning Commission
- b) Items discussed at the May 4, 2016 City Council Regular Meeting
- c) Set date, time and location for next meeting

6. Citizen's Participation: - 3 minute limit per citizen.

See "Rules for Citizen's Participation" under Item 3.

7. Adjournment

**AGENDA NOTICES:**

**Decorum Required:**

Any disruptive behavior, including shouting or derogatory statements or comments may be ruled out of order by the Presiding Officer. Continuation of this type of behavior could result in a request by the Presiding Officer that the individual leave the meeting, and if refused, an order of removal.

**Action by Council Authorized:**

The Commission may vote and/or act upon any item within this Agenda. The Commission reserves the right to retire into executive session concerning any of the items listed on this Agenda, pursuant to and in accordance with Texas Government Code Section 551.071, to seek the advice of its attorney about pending or contemplated litigation, settlement offer or on a matter in which the duty of the attorney to the governmental body under the Texas Disciplinary Rules of Professional Conduct of the State Bar of Texas conflict with the Open Meetings Act and may invoke this right where the City Attorney, the Mayor or a majority of the Governing Body deems an executive session is necessary to allow privileged consultation between the City Attorney and the governing body, if considered necessary and legally justified under the Open Meetings Act. The City Attorney may appear in person, or appear in executive session by conference call in accordance with applicable state law.


**Executive Sessions Authorized:**

This agenda has been reviewed and approved by the City's legal counsel and the presence of any subject in any Executive Session portion of the agenda constitutes a written interpretation of Texas Government Code Chapter 551 by legal counsel for the governmental body and constitutes an opinion by the attorney that the items discussed therein may be legally discussed in the closed portion of the meeting considering available opinions of a court of record and opinions of the Texas Attorney General known to the attorney. This provision has been added to this

agenda with the intent to meet all elements necessary to satisfy Texas Government Code Chapter 551.144(c) and the meeting is conducted by all participants in reliance on this opinion.

**Attendance By Other Elected or Appointed Officials:**

It is anticipated that members of the City Council, other city board, commissions and/or committees may attend the meeting in numbers that may constitute a quorum of the other city boards, commissions and/or committees. Notice is hereby given that the meeting, to the extent required by law, is also noticed as a meeting of the City Council, other boards, commissions and/or committees of the City, whose members may be in attendance. The members of the boards, commissions and/or committees may participate in discussions on the same items listed on the agenda, which occur at the meeting, but no action will be taken by such in attendance unless such item and action is specifically provided for on an agenda for that board, commission or committee subject to the Texas Open Meetings Act.

  
Shelley Goodwin, TRMC  
City Secretary

This is to certify that I, Shelley Goodwin, posted this Agenda at 12:05 pm May 5, 2016 on the bulletin board located at the entrance to the Garden Ridge City Hall, 9400 Municipal Parkway, Garden Ridge, Texas.

  
Shelley Goodwin, TRMC  
City Secretary

REC#: 00178975 5/03/2016 9:37 AM  
TRAN: 112.0000 P&Z VARIANCE FEES  
OPER: CASH TERM: 001  
REF#: SD1127  
REZONING FEE-SAHOTA HOLDINGS 500.00CR  
P&Z VARIANCE FILING

REC#: 00178975 5/03/2016 9:37 AM  
TRAN: 112.0000 P&Z VARIANCE FEES  
OPER: CASH TERM: 001  
REF#: SD1127  
MASTER PLAN-SAHOTA HOLDINGS  
P&Z VARIANCE FILING 550.00CR

Ordinance# 13-12008 City of Garden Ridge

Planning and Zoning Form 1  
APPLICATION FOR CHANGE OF ZONING  
(Type or Print)

1. Date: 4-19-2016 Case #: \_\_\_\_\_
  
2. Applicant Name: SAHOTA HOLDINGS, LLC; c/o RAVINDER SAHOTA  
(First) (Middle) (Last)
  
3. Mailing Address: PO BOX 592233  
(Street)  
SAN ANTONIO TX 78259  
(City) (State) (Zip)  
  
Phone: (830)- 832-7284
  
4. Applicant's relationship to property to be rezoned:  
Sole owner  Part owner  Other; \_\_\_\_\_  
(Specify)  
(If not sole owner, furnish a notarized letter of authorization from all owners as attachment 1.)
  
5. Property location: SW CORNER OF FM 2252 AND NACOGDOCHES LOOP  
(Street address or street property front)
  
6. Legal description:  
  
Plat: Lot(s) \_\_\_\_\_ Block(s) \_\_\_\_\_  
  
Subdivision; \_\_\_\_\_  
  
Acreage: 2.080 (If acreage, provide separate metes and bounds description as attachment 2.)  
  
Property Deed recorded in Comal County Volume # 791 Page # 388
  
7. Existing use of property: RESIDENCE-AGRICULTURE (RA) DISTRICT
  
8. Proposed use of property: COMMERCIAL ZONE - NEIGHBORHOOD SERVICE DISTRICT (B-1) FOR USE AS  
CONVENIENCE STORE & CAR WASH
  
9. Give dimensioned map with north orientation, scaled 100 or 200 feet per inch, of the property to be rezoned showing all streets and parcels of land within 300 feet of the property as attachment 3. Key each adjoining land parcel to a list of current owners and addresses as attachment 4.
  
10. Give site plan showing location, dimensions and uses of existing or proposed structures, easements, water sources, fences, curb cuts, street and alley right-of-way lines within one foot of property to be rezoned, on another map of larger scale, as attachment 5.
  
11. Identify any deed restrictions on agriculture, residential, business or other use. If none, so state: NONE

12. Reason for requesting zoning change (attach additional sheet if needed): \_\_\_\_\_  
 ZONING CHANGE IS NECESSARY TO CHANGE FROM RESIDENTIAL CLASSIFICATION TO COMMERCIAL USE TO ALLOW  
 FOR AN AUTOMOTIVE SERVICE STATION AND CAR WASH  
 \_\_\_\_\_  
 \_\_\_\_\_

13. The undersigned hereby requests that the property identified in this application be reclassified from: RESIDENCE-AGRICULTURE (RA) DISTRICT district to: COMMERCIAL - NEIGHBORHOOD SERVICE (B-1) district, in accordance with Garden Ridge City Ordinance 13. I consent to the posting of hearing notices on the said property. I understand that the information provided herein will be used by the City of Garden Ridge for sending required notices to adjacent property owners. I bear full responsibility and liability for any losses or costs incurred by the City, or others, caused by errors or omissions in this application.

14. Applicant Signature: Frank Sell

Attachments:

1. Owner(s) letters of authorization, if applicable
2. Metes and Bounds description of property, if applicable
3. Map of property
4. List of adjacent property owners
5. Site plan
6. Check for zoning change fee per Garden Ridge City Ordinance 11.

----- CITY USE ONLY -----  
 CHANGE OF ZONING

		Date
City Admin.:	Application received	_____
	Application verified	_____
	Fee received \$ _____ Check # _____	_____
	Application sent to P&Z	_____
P&Z:	Owners' acceptance of application	_____
	Notice to adjoining property owners'	_____
	Notice of public hearing	_____
	Public hearing conducted	_____
	P&Z decision on rezoning	_____
	P&Z recommendation to City Council	_____
City Council:	Notice to adjoining property owners'	_____
	Notice of public hearing	_____
	Public hearing conducted	_____
City Admin.:	Applicant notified of Council Decision	_____
	Zoning ordinance change published	_____



April 26, 2016

Ms. Nancy Cain  
City of Garden Ridge  
City Administrator  
9400 Municipal Parkway  
Garden Ridge, Texas 78266-2366

Re: Garden Ridge Center Convenience Store (Master Development Plan Narrative)

Dear Ms. Cain:

The attached narrative is to accompany the Master Development Plan seeking review/approval for Water Rights for the subject tract. The proposed tract is a 2.080 acre tract of land located at the southwest corner of FM 2252 and Nacogdoches Loop (Old FM 2252) within the City of Garden Ridge. The following subheadings discuss the various components that will be considered with the design and development of this tract.

**ZONING** – The current zoning for this property is Residence-Agriculture (RA) and is pending review/approval of rezoning to Commercial Zone – Neighborhood Service District (B-1) to allow use of this tract as a Convenience Store and Car Wash. The Convenience Store will encompass a Convenience Store (5,000 SF), a Fast Food Facility with drive-thru (1,200 SF), and Retail Space (1,500 SF), for a total gross area floor area of 7,700 SF. The Off-Street Parking criteria from the Zoning Ordinance was used to determine the minimum parking requirements, which is provided.

**DRAINAGE** – The site drains naturally from west to east and outfalls to a 48” CMP pipe under Old FM 2252. The proposed site will also drain primarily west to east with surface drainage across the parking lot and storm sewer drains/inlets and piping to capture runoff. The proposed storm sewer runoff will be collected onsite and outfall into a proposed detention basin sized to accommodate the 10, 25, and 100 year storm events with a peak rate of run-off (discharge) no greater than pre-existing 25-yr storm event as outlined in the Subdivision Platting Ordinance.

**SETBACKS, FAÇADE, LIGHTING, AND LANDSCAPING** – The design constraints outlined in the Zoning Ordinance for a Neighborhood Service District (B-1) shall be adhered to for the building height, front, side, and rear yard setbacks. The building façade will be of not less than 90% masonry or masonry veneer construction. Exterior lighting shall not aim beyond the owner’s property line nor illuminated adjoining Residential District lots to more than five (5) foot-candles measured at the point of highest intensity. The Site Lighting / Parking Lot Lighting will encompass LED bulbs which offers the advantages of lumen output, color rendering, and energy efficiency. Retaining walls shall be timber, concrete, concrete or brick masonry or stone. A

landscaping design will be included as part of the construction drawings submitted for a building permit and following the requirements outlined in Section 8.5 of the Zoning Ordinance. On the subject tract, oak trees ten (10) inch diameter and elm trees over eight (8) inch diameter or greater will be saved that do not overly the proposed building envelope, parking lot, driveways / drive aisles, or structures. A variance request will be submitted to the city for the no greater than one-third (1/3) of lot area for impervious cover.

UTILITIES – The site has availability of all utilities except for sewer. An on-site septic system will be designed following the Texas Commission on Environmental Quality (TCEQ) Chapter 285 – On-site Sewage Facilities Criteria. The aerobic system will be sized only to treat the washrooms from the convenience store, fast food facility, and retail space. The required separation distances will also be met. Discussions with the City Engineer will be required to determine the requirements for proposed water improvements planned for Nacogdoches Loop. The proposed water meter sizes are for the intended uses:

- Convenience Store, Lease Space, & Fast Food Facility: 1 ½" Meter
- Car Wash: 1" Meter
- Irrigation: ¾" Meter

ENVIRONMENTAL – The subject tract is located within the Edwards Aquifer Transition Zone. The proposed Convenience Store and Car Wash will be in compliance with the TCEQ Requirements for projects within this zone. As such, an Underground Storage Tank Facility Plan will be submitted and approved prior to construction of any underground storage tank. This will be required for both the underground fuel tank and the proposed car wash systems which employ underground tanks as well. The proposed Car Wash Equipment and Reclaim System will be self-contained and will not tie into the proposed septic system. Brochures of the Car Wash Equipment (Washworld Profile SoftTouch [ST]) and Reclaim System (Aqua Bio Technologies Bio Pro Complete 4000) have been included with the Master Development Plan Package.

SIGNAGE – The Site Signage / Business Advertising will comply with the city Signage Ordinance for the sign regulations in the (B-1) District.

We appreciate your time and consideration in this matter. Should additional information be required, please contact our office.

Sincerely,  
KFW Engineers



Andrew J. Barboza, P.E.  
Project Engineer

Enclosures

ATTACHMENT 02

EXHIBIT 'A'

File No.: 2077048-SA68 (SL)  
Property: FM 2252, 2.080 acres, Garden Ridge, TX 78266

**BEING 2.080 ACRES OF LAND, MORE OR LESS, OUT OF THE GEORGE M. DOLSON SURVEY NO. 96, ABSTRACT NO. 120, COMAL COUNTY, TEXAS AND BEING THE SAME PROPERTY CONVEYED IN A GENERAL WARRANTY DEED RECORDED IN DOCUMENT NO. 200006003784 AND DESCRIBED IN A SPECIAL WARRANTY DEED RECORDED IN VOLUME 791, PAGE 388, OFFICIAL RECORDS OF COMAL COUNTY, TEXAS, SAID 2.080 BEING MORE PARTICULARLY DESCRIBED BY METES AND BOUNDS AS FOLLOWS:**

**BEGINNING AT A MONUMENT FOUND FOR THE NORTHEAST CORNER OF THIS 2.080 ACRES, SAME BEING THE FIRST CHAMFER POINT AT THE INTERSECTION OF THE SOUTHWEST RIGHT-OF-WAY LINE OF FM 2252 AND THE NORTHWEST RIGHT-OF-WAY LINE OF NACOGDOCHES LOOP, SAME ALSO BEING THE POINT OF BEGINNING;**

**THENCE ALONG THE CUTBACK LINE, SOUTH 04 DEGREES 20 MINUTES 57 SECONDS EAST (CALLED SOUTH 04 DEGREES 36 MINUTES 18 SECOND EAST), A DISTANCE OF 65.41 FEET (CALLED 65.19 FEET) TO A MONUMENT FOUND FOR THE SOUTHEAST CORNER OF THIS 2.080 ACRES, SAME BEING THE SECOND CHAMFER POINT AT THE INTERSECTION OF THE SOUTHWEST RIGHT-OF-WAY LINE OF SAID FM 2252 AND THE NORTHWEST RIGHT-OF-WAY LINE OF SAID NACOGDOCHES LOOP;**

**THENCE ALONG THE NORTHWEST RIGHT-OF-WAY LINE OF NACOGDOCHES LOOP, SOUTH 61 DEGREES 29 MINUTES 32 SECONDS WEST (CALLED SOUTH 61 DEGREES 40 MINUTES 14 SECONDS WEST), A DISTANCE OF 345.34 FEET (CALLED 345.33 FEET) TO A POINT FOR THE MOST SOUTHERLY CORNER OF THIS 2.080 ACRES, SAME BEING THE SOUTHEAST CORNER OF THE LADSHAW PARTNERSHIP LTD 4.393 ACRES (DOCUMENT NUMBER 9606022876);**

**THENCE ALONG THE LINE COMMON TO THIS 2.080 ACRES AND SAID LADSHAW 4.393 ACRES, NORTH 30 DEGREES 35 MINUTES 15 SECONDS WEST (CALLED NORTH 30 DEGREES 24 MINUTES 33 SECONDS WEST), A DISTANCE OF 429.44 FEET (CALLED 428.91 FEET) TO A POINT FOR THE MOST NORTHERLY CORNER OF THIS 2.080 ACRES, SAME BEING THE NORTHEAST CORNER OF SAID LADSHAW 4.393 ACRES AND ON THE SOUTHWEST RIGHT-OF-WAY LINE OF SAID FM 2252;**

**THENCE ALONG THE SOUTHWEST RIGHT-OF-WAY LINE OF SAID FM 2252, SOUTH 74 DEGREES 53 MINUTES 08 SECONDS EAST (CALLED 74 DEGREES 42 MINUTES 26 SECOND EAST), A DISTANCE OF 535.55 FEET (CALLED 534.78 FEET) TO THE POINT OF BEGINNING, AND CONTAINING 2.080 ACRES OF LAND, MORE OR LESS.**


**A.P.N. 74432**



PROPOSED SITE



SCALE: 1" = 200'



Source: Esri, DigitalGlobe, GeoEye, DS, USDA, USGS, AEX, Getmapping, Aerogrid, IGN, IGP, swisstopo, and the GIS User Community, Esri, HERE, DeLorme, MapmyIndia, © OpenStreetMap contributors, Esri, HERE, DeLorme, MapmyIndia, © OpenStreetMap contributors, and the GIS user community, SGarza

THIS MAP WAS PRINTED USING THE GIS CLIENT SERVICE FROM KFW ENGINEERS & SURVEYING

**KFW**  
ENGINEERS + SURVEYING  
FIRM# 9513 FIRM# 10122300

14803 HUEBNER RD. BLDG. 40 SAN ANTONIO, TEXAS 78230 PHONE (210) 979-8444 FAX (210) 979-8441

ATTACHMENT 3  
PROPERTY OWNERS

REVISIONS: \_\_\_\_\_ ISSUE DATE: \_\_\_\_\_

DATE: April 2016  
DRAWN: AJB

SHEET: 1 OF 1



**ATTACHMENT 4**  
**Adjacent Property Owners**  
**Garden Ridge Center - 2.081 Ac Tract**  
**Garden Ridge, Texas**




<u>Num</u>	<u>Owner</u>	<u>Location Address</u>	<u>Mailing Address</u>	<u>Subd</u>	<u>Lot</u>	<u>Acreage</u>
1	Mark P. Howell	19295 FM 2252	19295 FM 2252 Garden Ridge, TX 78266		1	1.100
2	Voeller Properties LLC	19311 FM 2252	19311 FM 2252 Garden Ridge, TX 78266	Ashley Oaks Executive Center	1	0.815
3	Reunion Partners, LLC	19315 FM 2252	PO BOX 311323 New Braunfels, TX 78131	Ashley Oaks Executive Center	2	1.265
4	Overman Properties IV, LLC	19365 FM 2252	18965 FM 2252 Garden Ridge, TX 78266	Ashley Oaks Executive Center	3	2.726
5	Arrowood Mgmt LLC	19403 Arrowood Place	2511 N. Loop 1604 W, Ste 101 San Antonio, TX 78258	Arrowood Estates	20	1.146
6	Stephen F & Kyong S Elsdon	19407 Arrowood Place	19407 Arrowood Place Garden Ridge, TX 78266	Arrowood Estates	21	0.763
7	Ladshaw Partnership, LTD; c/o Harold A. Miller	Garden Ridge, TX 78266	8546 Marathon Dr. Universal City, TX 78148	A-120 Sur-9 G M DOLSON		4.393
8	Ladshaw Partnership, LTD	Schertz, TX 78154	393 Landa St. New Braunfels, TX 78130	A-120 Sur-9 G M DOLSON		6.494
9	Joan Catheryn Crowell	Garden Ridge, TX 78266	2402 Welsch LN New Braunfels, TX 78132	A-120 Sur-9 G M DOLSON		14.189



**LEGAL DESCRIPTION**  
 BEING 2.650 ACRES OF LAND, MORE OR LESS, OUT OF THE GEORGE M. DOLSON SURVEY NO. 94, ABSTRACT NO. 132, COMAL COUNTY, TEXAS AND BEING THE SAME PROPERTY CONVEYED IN A GENERAL WARRANTY DEED RECORDED IN THE DOCUMENT NO. 200504003784 AND DESCRIBED IN A SPECIAL WARRANTY DEED RECORDED IN VOLUME 174, PAGE 248 OFFICIAL RECORDS OF COMAL COUNTY, TEXAS


**BENCHMARKS**  
 BM # 1: SET 2" IN SQUARE IN THE CORNER OF A CONCRETE DRAIN STRUCTURE EAST OF THE SUBJECT SITE ON THE SAME SIDE OF FM 2252 ELEVATION = 832.33'  
 BM # 2: SET 2" IN SQUARE ON TOP OF CURB FROM A MEDIAN ISLAND ENTRANCE TO THE GARDEN RIDGE ESTATES NORTHWEST OF THE SUBJECT TRACT. ELEVATION = 887.52'

- COORDINATION NOTE:**
- CONTACT TWC (TIME WARNER CABLE) TO COORDINATE CABLE TV SERVICE. (210)-244-6200.
  - CONFIRM REQUIREMENTS AND COORDINATE WITH CPS (CITY PUBLIC SERVICE) FOR INSPECTIONS AND CONDUIT SIZES FOR PRIMARY AND SECONDARY ELECTRICAL SERVICES. (210)-353-2256.
  - CONTACT AT&T TO COORDINATE TELEPHONE SERVICE. 1-800-449-7923.
  - CONTRACTOR TO COORDINATE WITH CPS (CITY PUBLIC SERVICE) TO PLAN GAS SERVICES. (210)-353-2256.
  - CONTRACTOR TO COORDINATE WITH CITY OF GARDEN RIDGE WATER COMPANY TO PLAN WATER SERVICES. (210)-651-6832.
  - CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION.



**KEY NOTES**

- TYPICAL PARKING SPACES  
PARKING STRIPES
- PROPOSED SIDEWALK
- HANDICAP SIGN
- 6" STANDARD CURB
- HANDICAP PARKING SYMBOL
- CROSS HATCH STRIPING
- WHEEL STOP
- WHEELCHAIR RAMP DETAIL
- DUMPSTER ENCLOSURE
- PARKING LOT LIGHTING WITH LED BULBS
- CAR WASH EQUIPMENT  
WASH SYSTEM: WASHWORLD PROFILE ST.  
RECLAIM SYSTEM: AQUA BIO TECHNOLOGIES BIO PRO COMPLETE 400
- (1) MASTER PYLON SIGN NOT TO EXCEED 14 FT. IN WIDTH NOT TO EXCEED 16 FT. IN HEIGHT
- (1) BUSINESS ADVERTISING SIGN
- BUILDING FACADE WITH 90% OR GREATER MASONRY OR MASONRY VENEER FINISH
- RETAINING WALL - NO GREATER THAN 3 FT. IN HEIGHT
- STORE AND LEASE SPACE WATER METER (1" WATER)
- CAR WASH WATER METER (1" WATER)
- IRRIGATION METER (1/2" WATER)
- AIR/WATER STAND



**TRAFFIC SUMMARY TABLE**

LABEL	BUILDING USE	GROSS FLOOR AREA	OFF STREET PARKING REQ. RATIO	PARKING PROVIDED
A	Fast Food Facility	1,200 S.F.	1 : 100	12
B	Convenience Store	5,000 S.F.	1 : 200	25
C	Retail Space	1,500 S.F.	1 : 200	8
D	Car Wash	900 S.F.	N/A	-
TOTAL				45

**PROPOSED WATER METER SIZES**

BUILDING USE	GROSS FLOOR AREA	LuEs
Convenience store & Lease space	1 1/2" Water Meter	4.0
Car Wash	1" Water Meter	1.7
Irrigation	1/2" Water Meter	1.3



DATE: \_\_\_\_\_  
 REVISIONS: \_\_\_\_\_  
 THIS DOCUMENT IS RELEASED BY AUTHORITY OF CRAIG FLETCHER, P.E. # 90340 FOR INTERIM REVIEW ONLY AND NOT TO BE USED FOR CONSTRUCTION.

**GARDEN RIDGE CENTER CONVENIENCE STORE  
 GARDEN RIDGE, TX 78266  
 MASTER DEVELOPMENT PLAN**

JOB NO: 156-03-01  
 DATE: APRIL, 2016  
 DRAWN: M.C. CHECKED: C.F.

SHEET NUMBER:  
**1 OF 1**

**PROFILE**  
MAX

**PROFILE**  
ST



## Profile Soft Touch Vehicle Wash System

Washworld's Profile® is the soft touch system you've been waiting for. Combining Washworld's advanced technology used in our touch-free systems with the latest in washing materials, Profile is the answer to growing your car wash business. With standard features such as Washview® HMI On-Site, VS2® Vehicle Sizing System and Flex Pass® Dual Application System, Profile provides an exceptional value.

Your customers are sure to appreciate Profile as well.

The wall mounted system eliminates the gantry and presents a clean, open bay while Washworld's exclusive Digital Surface Profile (DSP) utilizes 3D imaging to insure optimal cleaning. Eye-catching LED lighting and audible voice prompts add to the experience.

Like all of Washworld's systems, Profile was designed with emphasis on durability, simplicity of use and reduced maintenance. Profile is your profit generator.

**WASHWORLD**

2222 American Blvd. | DePere, WI  
54115

920.338.9278 | 888.315.7253

# Profile With The Latest Technology

## Digital Surface Profile (DSP)

Washworld's exclusive DSP - Digital Surface Profile system is the advanced method of reading a vehicle's contours to allow for the most precise cleaning possible. Utilizing 3D imaging, DSP enables Profile to adjust for various vehicle surfaces to deliver a wash that reaches every angle with Profile's super soft polyethylene foam wash media. The dual side brushes are belt driven with independent movement while the variable frequency drive controls for the side and top brushes ensure a smooth operation. Profile's programmable Clean Rinse Wash Media Cleaning System keeps the brushes from retaining dirt and debris which results in the best possible customer experience.

The DSP System offers consistent length, width and height measuring of vehicles for optimal product application and cleaning by Profile. This ensures that products are applied to the vehicle not the floor, which saves money and reduces wash times by customizing the travel distance of the Profile based on the length of each individual vehicle.

## VS<sup>2</sup>® - Vehicle Sizing System

Especially important when positioning vehicles within a soft vehicle wash bay, Washworld's Vehicle Sizing System (VS<sup>2</sup>), with precise loading feature, utilizes advanced software coupled with photo eye technology to provide a safe and reliable means of positioning the vehicle in the wash bay. This eliminates the need for floor mounted treadle plates or wheel stops, resulting in a significant reduction in wiring and fewer components to maintain.



## Solution Delivery System (SDS)

The Profile Solution Delivery System comes loaded with standard features:

- Multi-Stage solution delivery system which is capable of up to 225psi
- Composite direct injection/no drift chemical metering system
- Eight (8) low pressure chemical injectors which allows for any two products to be applied simultaneously in a single wash pass
- Multiple coupling joints for ease of maintenance
- Standard product application includes pre-soak one, pre-soak two, protectant, and sealant

## Flex Pass™ - Dual Application System


Profile's Dual Flex Pass application system provides complete coverage of a vehicle's sides and top simultaneously. Programming allows for front (exit) mounted pods and rear (entrance) mounted pods individually or concurrently to apply pre-soaks, protectants, sealants and rinse, with the ability for two products to be applied during a single pass of the vehicle. The Dual Flex Pass means:

The ultimate in time savings = More vehicles per hour = Greater return on investment!


## Washview® HMI On-Site & Washview HMI Remote™

A color touch screen gives you complete access to Profile in order to turn functions on or off, including programming, maintenance, diagnostics, and view wash counts. No on-site PC or laptop is needed to configure your wash. Profile also features a comprehensive integrated security system which can monitor auto cashiers, doors, fluid levels and more. In addition the Wash Package Storage capability allows for up to eight wash packages to be retained which can be quickly copied to the immediate wash setup.

The revolutionary design of our Washview HMI Remote features the same cutting edge technologies as Washview with the additional ability to receive e-mail or text message alerts from anywhere in the world using your Tablet or Smart Phone (application requires additional purchase from iTunes or Google Play). Washworld's exclusive Washview HMI Remote software allows you to access Profile from anywhere using your PC, laptop, tablet or Smart Phone.

A large graphic of a globe with the "WASHWORLD" logo overlaid in white, bold, sans-serif font. The globe shows the Americas and parts of Europe and Africa.

**WASHWORLD**



Digital Surface Profile - DSP



VS<sup>2</sup> for Profile

# Profile With Quality Built In

## Stainless Steel

There is no better material to use in a wash environment than stainless steel and it is utilized throughout Profile. The stainless steel used for Profile's wall mounting system, travel rails, and laser cut overhead wash carriage, ensures that Profile is the most long lasting and durable system in the industry.

## Energy Chain

Profile incorporates the latest in energy chain design available for handling of product delivery, controls and communication needs. Our composite energy chain is factory loaded with solution supply lines and control wiring. Profile includes a factory wired bay box for ease of installation which also reduces the installation cost. Available as driver or passenger side mount, E-chain provides a clean appearance in the wash bay and also a low maintenance way to route hoses, wires, and communication cable to the wash unit.

## The Profile Advantage

Designed to increase profits by reducing operating and maintenance costs, Profile features:

- Energy efficient TEFC climate proof motors
- Sealed gearboxes to eliminate oil changes
- High quality, premium fiberglass enclosures to withstand harsh wash bay conditions for a longer life
- Minimal rolling resistance for improved efficiency
- Positive dual belt carriage drive for accurate tracking and smooth motion
- A hand held remote control replaces a joystick box for manual movement of Profile functions
- For colder climates, an in-bay temperature monitoring system will automatically disable the wash bay if temperatures reach a preset threshold
- Profile is Wash Activation and Customer Buy Up ready
- Multi application of products in a single pass with reduced wash package time means more cars per hour



## Customer Appeal

From the minute that your customers drive into your wash bay, they will see that Profile is a different kind of soft wash. Profile's wall mounted system keeps the machine up off the floor and creates an open and inviting wash bay. High gloss composite wash carriage and side brush covers with sleek graphics and LED lighting give Profile a clean and refined look.

As your customers proceed into the bay, audible voice prompts combine with dual machine mounted multi-colored LED light bars to position the vehicle in the bay. As the wash progresses, the voice prompts inform your customer of product applications which coincide with the optional in-bay instructional sign.

The proof of any system is in how well it cleans. With Profile's three brushes guided by DSP, your customers' vehicles receive optimal cleaning. Optional Power Clean Side Blasters with touch or touch-free wheel cleaners combine for a value added service your customers will appreciate.

Profile is a sure way to keep your customers coming back and a certain way to increase your bottom line.




## STANDARD FEATURES

- Stainless Steel Wall Mounting System
- 34' Stainless Steel Travel Rails
- Stainless Steel Laser Cut Overhead Wash Carriage
- High Gloss Composite Wash Carriage Covers
- High Gloss Composite Side Brush Covers
- VS<sup>2</sup> - Vehicle Sizing System with Precise Loading Feature
- DSP (Digital Surface Profile) Technology
- Super Soft Polyethylene Foam Wash Media (Top and Side Brushes)
- Programmable Clean Rinse, Wash Media Cleaning and Lubricating System
- Belt Driven Dual Side Brush with Independent Movement
- Positive Drive Dual Belt Carriage Motion
- TEFC/Climate Proof Motors and Gearboxes with Minimal Rolling Resistance
- Variable Frequency Drive Controls for Smooth Top and Side Brush Operation
- Composite E-Chain
- Driver or Passenger Side E-Chain Supply
- Dual Flex Pass Application System- Complete Coverage-Sides and Top
- In-Bay Audible Voice Commands
- Dual Machine Mounted 78" Multi-Colored LED Entrance Side, Light Bars
- Multi-Stage Solution Delivery Pump (Capable of up to 225 PSI)
- Composite Direct Injection/No Drift Chemical Metering System
- (8) Low Pressure Chemical Injectors
- Washview HMI On-Site Controller
- Comprehensive Integrated Security System
- Wash Package Storage
- Hand Held Remote Control for Manual Movement and Machine Functions
- In-Bay Temperature Monitoring System
- Wash Activation and Customer Buy Up Ready


## OPTIONS

- Tri-Foam Pods - Two Sets (1 Set Entrance, 1 Set Exit Mounted)
- Extended Solution Delivery (ESD) with 4 Injectors (1 Each for Bug A'Salt and Wheel Cleaner, 2 for Foam Polish)
- Power Towers - Six Nozzle Configuration Only Available on High Pressure Models
- Reclaim Adapter on High Pressure Models
- Stainless Steel Undercarriage Manifold (Medium or High Pressure)
- High Pressure Delivery System - Ultra Compact Pump Station
- Washview HMI Remote (Remote High Speed Connectivity)
- Entrance and In-Bay Directional/Service Confirmation Signs (12 or 24 Volt)
- Dryer Systems - Unlimited Configurations Available
- LED Countdown Timers
- Custom Color Wash Media
- Powerclean Side Blasters with Touch Wheel Cleaner
- Powerclean Side Blasters with Touch-Free Wheel Cleaner
- Door Controls - Independent (Entrance and Exit) Control
- Water Treatment Equipment

© 2015 Washworld, Inc.



Profile  
Ultimate Control Cabinet



Medium Pressure  
Solution Delivery System (SDS)  
Shown with Optional  
Extended Solution Delivery (ESD)

Optional Ultra Compact  
High Pressure  
Delivery System



## SPECIFICATIONS

Equipment Envelope Requirements does not include obstructions, etc.


Bay Height.....	11'	minimum
Bay Width	Wall Mounted Energy Chain....	15' 4" minimum
Bay Length	Recommended.....	37' 4" minimum

## PROFILE UTILITY REQUIREMENTS

Utility Requirements for standard Profile ST does not include options or other equipment requirements

Air: .....	13 CFM @ 40 PSI (with Tri-Foam)
Water: .....	15 GPM @ 40 PSI with 1" supply
Electrical: .....	30 Amps, 3 phase, 208/230 V

*Note: Specifications Subject to Change Without Notice. The decibel level of the dryer (measured at 1.6 meters from the floor and 1 meter from the surface) is 94dB. The decibel level of the pump station measured at 1.6 meters from the floor and 1 meter from the surface) is 84dB for high pressure and 72dB for low pressure. Decibel levels are impacted by surrounding materials and conditions and will vary.*



# BIO-PRO COMPLETE "WATER RESTORATION SYSTEM"

## BIOLOGICAL WASTE WATER RESTORATION SYSTEMS

*Water is and will always remain the lifeblood of the vehicle wash industry.* Without water our industry will no longer exist! Water shortages have been experienced throughout the world and the cost of obtaining fresh water and the discharge of waste water have continued to rise. Cities have continually raised prices on water and sewer with no end in sight. These increases will continue to negatively impact the profits of vehicle wash sites and some day force them out of business unless action is taken to treat and reuse waste water.

## NATURE'S WAY

*We take our direction for waste water treatment from nature.* In our environment the natural process of cleaning waste is through the utilization of aerobic bacteria to consume waste. Sewer treatment systems have incorporated this technology for years. By bringing this approach to the vehicle wash industry, the natural process of biologically breaking down used vehicle wash chemicals into CO<sub>2</sub> and H<sub>2</sub>O will dramatically reduce a washes fresh water intake and sewer discharge costs.

**AQUA BIO<sub>i</sub>**  
TECHNOLOGIES 

## THE NATURAL PROCESS OF WATER RESTORATION

### SOLIDS SEPARATION

*In any vehicle wash, solids coming off the vehicles need to be settled out in settling tanks where the solids can be collected and hauled away.* Gravity is free, so by letting gravity settle out the solids in this process, solid separation is not done with pumps and electricity.

### AERATION

After the waste water exits the settling tanks where the largest solids have settled out, the water enters an aeration chamber which is the first step in a biological treatment process. In this chamber the air is infused in the water to not only emulsify the chemicals it's also used to begin the transformation of the natural anaerobic bacteria into becoming aerobic bacteria. In doing so the aerobic bacteria can be used in the next process to consume chemical waste and prevent the water from developing an odor when reused. This water, once aerated, is then pumped up into the equipment room by means of vortex pumps to be run through hydro cyclones.

### CYCLONIC SEPARATION

The water that's pumped from the aeration tank is sent through hydro cyclones which cyclonically separate any remaining solids down to 5 micron. The separated solids are sent back to the first settling tank where they are collected for haul away. The cleaned water is then sent to the bio tank for the removal of chemicals.

*See reverse side for an explanation of the treatment process.*

# BIO-PRO COMPLETE "WATER RESTORATION SYSTEM"



## BIOLOGIC CONSUMPTION

There are several things going on in the bio chamber with the first being additional aeration. Aeration insures that the bacteria that will be grown in this tank are aerobic. Aerobic bacteria are 90 percent more aggressive in consuming waste in the water than anaerobic bacteria are. These aerobic bacteria attach to the bio media which fill the bio tank. With the bio tank filled with bio media, the water containing the used vehicle wash chemicals will come in contact with the active bacteria whereby the bacteria will consume the chemicals from the water. The byproduct of this natural consumption of chemicals by the bacteria will be CO<sub>2</sub> and H<sub>2</sub>O which is nonhazardous.

## CLARIFICATION

In the clarification chamber the bio sludge coming from the bio chamber is allowed to settle to the bottom of this tank so that it can be pumped to sewer once a day.

## CLEAN WATER HOLDING TANK

After the clarification tank, the water gravity overflows into the clean water tank where it's stored for reuse in the vehicle wash. In a biologic water restoration system, the water needs to continuously circulate so that the natural bacteria are always in the presence of aeration to keep the bacteria aerobic. If the vehicle wash is closed or is not washing vehicles the bio -system switches into an energy saving mode which turns off most all higher horsepower pumps and turns on a recirculation pump that pumps the water from the clean water tank back into the bio chamber to start the process over again. This energy-saving mode reduces the power consumption by 75 percent.



## WATER QUALITY EXPECTATION

When using the Bio-Pro Complete Water Restoration System the restored water should reach the water quality levels shown below:

- Oxygen levels higher than 60%
- Oil emulsion levels of less than 5 ppm
- PH levels between 6.5 – 8.0
- COD reduction to 1:10
- BOD levels less than 150 mg/l

As for the overall TDS levels, these levels can vary based on the level in the incoming city water. Variations can also be found in the winter when salts and de-ice chemicals are used on the roads.

The turbidity may change based on the amount of dye remaining in the water which has come from colored foam chemicals used. Dyes are biodegradable but will take more time to break down than wash chemicals. The water may have a slight tint of green or blue but this coloration will not impact the performance of the water when reused.

## SYSTEM CONFIGURATIONS

The Bio-Pro Complete Water Restoration System can be installed in the following configurations:

- **Above Ground** where equipment room space is available
- **Below Ground** in either concrete or fiberglass tanks

## CAPACITY SIZES

Water restoration systems can be custom-built to any capacity or they come standard in sizes of 3,000 – 4,000 – 6,000 – 10,000 and 20,000 gallon per hour. Larger sizes can be designed and built to order.

## SIZING SYSTEMS

When sizing a water restoration system it's important that the following is known:

- Maximum gallons of water used per vehicle
- Maximum number of vehicles that can be washed per hour, per wash bay
- The maximum amount of chemicals used per vehicle wash


AQUA BIO TECHNOLOGIES, LLC.

3730 Sleeth Road  
Commerce, MI 48382  
Ph (248) 529-3404  
Fax (248) 684-4070  
Email [info@aquabio.co](mailto:info@aquabio.co)  
Web [www.aquabio.co](http://www.aquabio.co)

EXAMPLE OF BIO PRO COMPLETE SYSTEM AND INSTALLATION



BIO COMPLETE SYSTEM



Air Quality



**100%  
RECYCLED  
WATER**

We are committed  
to water conservation and  
environmental protection.



ete



FIBERGLASS TANK INSTALLATION



SETTLING TANK INSTALLATION

EXAMPLE OF BUILDING FINISHES





VALERO  
sell

TONY'S PAINTS  
FREE ESTIMATES  
(210) 669-2443  
www.tonyspaints.com

TONY'S PAINTS  
(210) 669-2443

VALERO

VALERO

VALERO

VALERO

25.98  
GAL

FIRE LINE DO NOT PROCEED BEYOND THIS LINE

Food & Fuel  
express



FIRE LANE NO PARKING THE SIGN IS HERE



ProckFuel

IDEALLEASE

FIRE LANE NO PARKING TOW AWAY ZONE

FIRE LANE NO PARKING TOW AWAY ZONE



IDEALEASE

WASHWORLD

FIRE LANE NO PARKING TOW AWAY ZONE

FIRE LANE NO PARKING TOW AWAY ZONE



## City of Garden Ridge

9400 Municipal Parkway  
Garden Ridge, Texas 78266-2600  
(210) 651-6632  
Fax (210) 651-9638

**MINUTES OF JOINT CITY COUNCIL AND  
PLANNING AND ZONING COMMISSION MEETING,  
APRIL 12, 2016**

**Councilmembers Present:**

Mayor Nadine Knaus  
Councilmember Todd Arvidson  
Councilmember Bryan Lantzy  
Mayor Pro-Tem John McCaw  
Councilmember Larry Thompson  
Councilmember Shelby Trial

**Member Absent:**

None

**Commissioners Present:**

Chairman Sam Stocks  
Vice Chairman Frank Dansby  
Commissioner Kay Bower  
Commissioner Greg Czerniak  
Commissioner David Heier  
Commissioner Kitty Owen  
Commissioner Shawn Willis

**Commissioners Absent:**

None

**City Staff Present:**

Nancy Cain, City Administrator  
Shelley Goodwin, City Secretary

**1. Call to Order**

With a quorum of the City Councilmembers present and a quorum of Planning and Zoning Commission Members present, Mayor Knaus called the joint meeting of the Garden Ridge City Council and Planning and Zoning Commission to order at 6:00 p.m. on Tuesday, April 12, 2016, in the City Council Chambers of the Garden Ridge City Hall, 9400 Municipal Parkway, Garden Ridge, Texas 78266.

**2. Citizen Comments – limited to 3 minutes each**

No one wished to speak.

### **3. Business Items**

#### **a) Presentation by UTSA of the Comprehensive Master Land Use Plan update for the City of Garden Ridge**

Dr. Richard Tanger introduced himself and Dr. Durlock whom have both worked on the Comprehensive Master Land Use Plan. Dr. Tanger presented a PowerPoint of the progress of the Plan (see attached).

The City Council and Planning and Zoning Commission discussed the Schertz Industrial Park changing, Lone Star Rail timeline, sewer, and the need for the widening of FM 2252.

The residents of Garden Ridge that were in attendance asked questions regarding the location of the Lone Star Rail, growth rate for Garden Ridge, alternative housing, and other types of businesses that would fit in Garden Ridge.

Dr. Tanger stated growth is coming, but the City can control their destiny. He stated the Comprehensive Master Land Use Plan would include the entire City of Garden Ridge. He stated he is proposing Garden Ridge would want to have connectivity to the Lone Star Rail Station, which would be an asset to the residents of Garden Ridge. He also stated he feels alternative housing would allow for a walkable and bike-able city.

Mayor Knaus stated the closer the completion of the Plan, there would be more opportunities to ask questions and review the proposed Plan.

#### **b) Planning and Zoning Commission Recommendations and Possible Action to City Council:**

- i. Request regarding a petition by The Club at Garden Ridge, 21320 Water Wood Dr., for variance to Ordinance 55, Section 7 for the placement of small directional and parking signs at various locations in Garden Ridge for the purpose of directing wedding and special event guests to the venue and parking. Placing the signs 48 hours prior to the event and removing signs 12 hours after the event.**

##### **a. Approval or Disapproval**

Kristi DeBaun, The Club at Garden Ridge, stated The Club at Garden Ridge is requesting a variance for the placement of small directional and parking signs at different locations. She stated the signs would be set up 48 hours before an event and be removed 12 hours after an event. She reviewed 7 proposed locations and discussed the difficulty people have in finding The Club at Garden Ridge. These proposed locations would eliminate people from driving around the neighborhoods lost.

The Planning and Zoning Commission discussed alternative sign options, requested timeframe, permission from property owners, and directional maps.

**Motion:** Upon a motion made by Commissioner Czerniak and a second by Commissioner Heier, to postpone this items until the proposed locations of the signs that property owners have given permission for the placement, the design of the signs are more in alignment with the United States Department of Labor Occupational Safety & Health Administration Uniform Traffic Control Devices (MUTCD) for visibility after dark, and the requested timeframe has been scaled down. The Planning and Zoning Commission voted five (5) for, one (1) opposed (Dansby). The motion carried.

**c) City Council discussion and take Possible Action:**

- i. Request regarding a petition by The Club at Garden Ridge, 21320 Water Wood Dr., for variance to Ordinance 55, Section 7 for the placement of small directional and parking signs at various locations in Garden Ridge for the purpose of directing wedding and special event guests to the venue and parking. Placing the signs 48 hours prior to the event and removing signs 12 hours after the event.**
  - a. Approval or Disapproval**

Since the previous Agenda Item was postponed, this Agenda Item was not necessary.

**4. Administrative Items**

**The Commission may discuss, consider and/or take possible action on the following items:**

**a) Minutes of the March 8, 2016 Regular meeting of the Planning and Zoning Commission**

**Motion:** Upon a motion made by Commissioner Dansby, and seconded by Commissioner Owen, to approve the minutes of the March 8, 2016 Regular Meeting of the Planning and Zoning Commission with corrections. The Planning and Zoning Commission voted six (6) for, none (0) opposed. The motion carried unanimously.

**b) Items discussed at the April 6, 2016 City Council Regular Meeting**

Sam Stocks, Chairman, stated David Penscik pulled his petition request for rezoning from B2 to L1. He also stated that the City Council approved the Planning and Zoning Commission recommendation for approval of the Preliminary Plat for Woodlands of Garden Ridge, Unit 3.

**c) Set date, time and location for next Planning and Zoning Commission meeting**

Tuesday, May 10, 2016 at 6:00pm.

**5. Citizen's Participation - 3 minute limit per citizen.**

**See "Rules for Citizen's Participation" under Item 3.**

Ken Knuepper, Schoenthal Road, stated he feels placement of signs for The Club of Garden Ridge would be helpful to eliminate lost people driving around the City. He also stated he attended a Comal ISD meeting where an announcement was made regarding Garden Ridge Elementary reaching its limits of students and they will be requesting portable buildings be

placed at the school. He also encouraged residents to be careful who they vote for on the School Board, because decisions are being made have a large impact on Garden Ridge.

**6. Adjournment**

**Motion:** Upon a motion made by Commissioner Dansby and a second by Councilmember Arvidson, the meeting was adjourned at 7:30 p.m.

---

Nadine L. Knaus, Mayor

---

Sam Stocks, Chair

ATTEST:

---


Shelley Goodwin, TRMC  
City Secretary

# City of Garden Ridge, Texas




Center for Urban and Regional Planning Research  
The University of Texas at San Antonio

# Existing Land Use



# Existing Zoning





**Legend**  
Garden Ridge, TX




Google earth

© 2016 Google



2 mi



Legend  
Garden Ridge, TX

Garden Ridge, TX

Scheanthal Rd

Binschelm

Barlowe Rd

Evans Rd

Marbach Ln

Alvarado Heights Rd

2252

3009

1337

382


Google earth

© 2016 Google





1 mi

Population 2000



Population 2010











# Comal County Population Trends

Comal County, Texas: Historical and Projected Population 1980-2040




# Population Trends 1980 - 2040

**Garden Ridge, Texas: Historic and Projected  
Population 1980-2040**



# Population by Age Cohort



# Gap Analysis

Industry Group	Demand (Spending)	Supply (Sales)	Retail Gap or Surplus	Leakage or Surplus
Motor Vehicle & Parts Dealers	\$22,438,714	\$0	\$22,438,714	100.0
Furniture & Home Furnishings Stores	\$2,813,957	\$0	\$2,813,957	100.0
Electronics & Appliance Stores	\$4,919,528	\$1,531,177	\$3,388,351	52.5
Bldg Materials, Garden Equip. & Supply Stores	\$5,689,762	\$2,853,277	\$2,836,485	33.2
Food & Beverage Stores	\$17,310,123	\$8,599,849	\$8,710,274	33.6
Health & Personal Care Stores	\$5,401,495	\$3,700,717	\$1,700,778	18.7
Gasoline Stations	\$6,291,337	\$2,957,144	\$3,334,193	36.1
Clothing & Clothing Accessories Stores	\$4,347,070	\$105,121	\$4,241,949	95.3
Sporting Goods, Hobby, Book & Music Stores	\$2,888,292	\$903,658	\$1,984,634	52.3
General Merchandise Stores	\$18,914,618	\$0	\$18,914,618	100.0
Miscellaneous Store Retailers	\$4,345,982	\$3,306,683	\$1,039,299	13.6
Nonstore Retailers	\$2,184,864	\$582,817	\$1,602,047	57.9
Food Services & Drinking Places	\$10,865,519	\$124,982	\$10,740,537	97.7

# Gap Analysis City of Garden Ridge

<b>Subject</b>	<b>Garden Ridge</b>	<b>Schertz</b>
Estimated Population 2015	3,606	36,726
Estimated Households 2015	1,374	13,324
Consumer Expenditures	\$108,411,261	\$637,777,506
Retail Sales	\$24,665,425	\$360,754,617
Retail Gap or Surplus	\$83,745,836	\$277,022,889
Leakage or Surplus Factor	62.9	27.7
Number of Businesses	13	186
Consumer Expenditures per household	\$78,902	\$47,867
Retail Sales per household	\$17,952	\$27,076
Retail Gap or Surplus per household	\$60,950	\$20,791

# Employment & Income City of Garden Ridge

<b>ECONOMIC CHARACTERISTICS</b>						
<b>Subject</b>	<b>Texas</b>		<b>Comal County</b>		<b>Garden Ridge</b>	
	Estimate	Percent	Estimate	Percent	Estimate	Percent
<b>EMPLOYMENT STATUS</b>						
Estimated Population 16 years and Over	19,858,082	100.0%	92,147	100.0%	2,800	100.0%
In Labor Force (incl. Armed Forces)	12,889,163	64.9%	56,137	60.9%	1,458	52.1%
Civilian	12,791,590	64.4%	55,931	60.7%	1,451	51.8%
Armed Forces	97,573	0.5%	206	0.2%	7	0.3%
Not in Labor Force	6,968,919	35.1%	36,010	39.1%	1,342	47.9%
Estimated Civilian Labor Force	12,791,590	100.0%	55,931	100.0%	1,451	100.0%
Percent Unemployed	(X)	7.7%	(X)	6.1%	(X)	5.1%
<b>INCOME AND BENEFITS</b>						
	Estimate	Percent	Estimate	Percent	Estimate	Percent
Estimated Median Household Income*	\$52,576	(X)	\$64,987	(X)	\$134,309	(X)
Estimated Total Households	9,013,582	100.0%	43,063	100.0%	1,312	100.0%
With SNAP Benefits in Past 12 Months	1,218,803	13.5%	3,034	7.0%	18	1.4%

\* = 2014 Inflation-Adjusted Dollars





malCoba Teran

